

**SBW over US 31 & Exit 72 Bridge Repairs**  
**BRIDGE DECK OVERLAY, SUPERSTRUCTURE, AND SUBSTRUCTURE REPAIRS**

PAY ITEM #	ITEM	UNIT	TOTAL	UNIT PRICE	TOTAL COST
202-02240	PAVEMENT REMOVAL	SYS	3782		
202-51368	SLOPEWALL REMOVAL	SYS	134		
202-91385	INLET, REMOVE	EACH	4		
202-94954	BARRIER WALL, CONCRETE, REMOVE	LFT	50		
205-06933	TEMPORARY INLET PROTECTION	EACH	1		
205-06937	TEMPORARY SILT FENCE	LFT	2805		
205-12108	STORMWATER MANAGEMENT BUDGET	DOL	11000		
205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	LS	1		
205-12618	SWQCP PREPARATION	LS	1		
207-09935	SUBGRADE TREATMENT, TYPE 1C	SYS	168		
211-09264	STRUCTURAL BACKFILL, TYPE 1	CYS	112		
214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	SYS	168		
302-06464	SUBBASE FOR PCCP	CYS	32		
306-08036	MILLING, ASPHALT, 2 IN.	SYS	1600		
	QC/QA-HMA, 4, SURFACE, PER GC MIX DESIGN	TON	352		
502-06329	PCCP, 12 IN	SYS	308		
503-12477	TERMINAL JOINT, TYPE HMA	LFT	68		
606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	LFT	1440		
602-01064	CONCRETE BARRIER	LFT	50		
609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	SYS	164		
616-06455	SLOPEWALL	SYS	169		
621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	EACH	1		
703-06029	REINFORCING BARS, EPOXY COATED	LBS	9490		
703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	EACH	98		
704-51002	CONCRETE, C, SUPERSTRUCTURE	CYS	4		
704-51106	DECK DRAIN	EACH	4		
709-12077	FIBER WRAP CONCRETE CASING SYSTEM	SFT	184		
709-51821	SURFACE SEAL	LS	1		
710-09158	PATCHING CONCRETE STRUCTURES	SFT	192		
715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	LS	1		
722-01066	HYDRODEMOLITION	SYS	1768		
722-12380	BRIDGE DECK OVERLAY, BUDGET	DOL	22000		
722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	SYS	1668		
722-12732	LONGITUDINAL GROOVING	SYS	1668		
722-51401	BRIDGE DECK PATCHING, FULL DEPTH	SFT	2800		
722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	SYS	1668		
722-51874	OVERLAY DAM	SFT	108		
724-12774	BRIDGE EXPANSION JOINT, TYPE SS, REPLACE	LFT	116		
801-06710	FLASHING ARROW SIGN	DAY	628		
801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	EACH	11		
801-11642	TEMPORARY TRAFFIC BARRIER, TYPE 2	LFT	3250		
801-12503	TEMPORARY TRAFFIC BARRIER, RELOCATE	LFT	2800		
808-06716	LINE, REMOVE	LFT	500		
808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	LFT	500		
808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	LFT	500		
801-04308	ROAD CLOSURE SIGN ASSEMBLY	EACH	2		
801-06625	DETOUR ROUTE MARKER ASSEMBLY	EACH	2		
801-06640	CONSTRUCTION SIGN, A	EACH	54		
801-06645	CONSTRUCTION SIGN, B	EACH	9		
801-07118	BARRICADE, III-A	LFT	56		
801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	EACH	2		
808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	LFT	1824		
808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	LFT	480		
808-12353	LINE, MULTI-COMPONENT, DOTTED, WHITE, 6 IN.	LFT	1090		
808-12781	LINE, MULTI-COMPONENT, SOLID, WHITE, 10 IN.	LFT	1335		
Subtotal Cost					
110-01001	MOBILIZATION & DEMOBILIZATION (8%)	LS	1		
801-06775	MAINTAINING TRAFFIC (5%)	LS	1		
Subtotal Cost					
306-08036	MILLING, ASPHALT, 2 IN.	SYS	23682		
406-05520	ASPHALT FOR TACK COAT	TON	9		
	QC/QA-HMA, 2, 58D, SURFACE, 9.5 mm	TON	5211		
Subtotal Cost					
<b>TOTAL Final COST</b>					